

LAKSHMIPRIYA BUILDER SPECIFICATION

The base cost of construction of residential House for Rs. 2200/= (Rupees Two Thousand Two hundred only) which includes the following mentioned works with material supply and construction labour charges. Additional cost/extra chargeable works has mentioned where ever applicable.

➤ **BASEMENT:**

- Earthwork Excavation from 5feet from lowest original natural ground level as per engineer's drawing.
- Basement height from natural ground level will be at 3.0 feet.
- Earth beam concrete height 1'-3", Fly ash brick work height 1'-9", total 3'- feet basement height.
- Basement & Septic tank brick work will be provided by Fly ash brick.
- Extra cost will be charged if additional height required by client above 2.0 feet.
- Sizes of foundation, column & reinforcement details are as per Engineer's design.
- Footing Column and Plinth Beam will be laid with 1:2:4.
- Reinforcement rod will be with ISI 550 grade Steel rods.
- If client wants other higher cost brands, the cost difference shall be borne by client.
- Material & Labour shed included.
- All the structural work will be carried out as per structural detailers from consultant Open well foundation depth 5'-0 feet.
- SBC of soil to be more than 180Kn/m² maximum 2.5 Kg/Sq. ft height of steel considered.

➤ **SUPERSTRUCTURE:**

- Ground floor to terrace Column, Roof Slab and Beam will be laid with Concrete Grade1:2:4.
- Chettinad cement will be used for construction.
- Superstructure champer brick work will be used.
- All RCC works of column, slab & beams will be as per engineer's design.
- Lintels will be continuous for 4.5inch brick wall & discontinuous for 9inch brick wall.
- Lintel and Sunshades bearing will be adopted as 9" on each side.
- Projection of Sunshade will be done up to 2feet.
- Peripheral/Outer Brick wall will be with 9" thick 1st Quality bricks with cement M- sand mortar ratio1:6.
- Floor to Floor height will 10feet high which includes 5inch thick floor/roof slab.
- All Hoop Iron or 8mm dia MS rod will be placed for every 5 layers in 4.5" thickness Brick wall with cement M- sandmortar1:4.
- Ceiling plastering will be done with Cement P- sand mortar ratio1:3.
- Internal Plastering (Iron mesh will be provided on concrete and block work joints) will be done with cement P- sand mortar ratio 1:5 where applicable.

- External plastering (Iron mesh will be provided on concrete and block work joints) will be done with cement P- sand mortar ratio 1:6 where applicable.
- Terrace Parapet will be of 3 feet high with 4.5" thickness brickwork.
- Windows Sill concrete of 50mm thick with allowable bearing of 9" on each side.
- Window sill concrete in external wall will be 3 feet high from floor level.
- Each room will be provided with 2 feet wide one side loft slab and brick wall cupboard fixed with Cuddapha slab.
- Cupboard size (4'-0" x 1'-3" x 7'-0").
- All curing works for brick works, RCC works, floor earth filling with consolidation.

➤ **JOINERY:**

- Main Door Frames will be provided with First Class Ghana Teak Wood of thickness 5" x 3", single panel shutter door with thickness 32mm (Height - 7 feet) Polished Standard design, Main door side borders, design carving are under extra costs. Lock will be of Godrej make.
- Main door size 3'-6" x 7'-0".

Accessories List for Main Door:

- Lock 1 No (Godrej Make) at cost Rs.2000/- to Rs.2500/-
- Tower bolt -8"-1 No.
- Tower bolt 6"-1 No.
- Door stopper -1 No (Magnet)
- Lens-1 No.
- Door Bush-1 No.
- Hinge-4 Nos.
- All internal Doors will be provided with 4"x2.5" flush shutters with Paint finish/skin/membrane shutters fixed in Gana Teak wood frame.

Accessories List for Bedroom:

- Lock-1 No. (Handle Lock)
- Tower bolt -8"-1 No.
- All internal Doors will be provided with 4" x 2.5" flush shutters with Paint finish size (3'-0" x 7'-0").
- Toilet Doors will be provided with PVC Doors and Frames (2'-6" x 7'-0")
- All window will be provided with UPVC Slider model with glass lens.
- UPVC Ventilators will be provided with Pinned glass lever type.
- Note: no specific door for kitchen area, pooja cupboard or pooja room.

➤ **PLUMBING:**

- Toilet Internal Pipe Lines will be provided with PVC for Hot water and CPVC for Cold water.
- Kitchen and Utility Pipe Lines Will be laid with PVC Pipes 4" - 4 Kg pipe.
- EWC/IWC/WB Fixtures make: Hindware, Somany.
Master Bedroom-Ordinary EWC Floor mounted with Slim Line tank & Seat cover.
- Wash Basin - Basic model (If clients prefer other brands from basic model extra charges will be applicable) Wall Mixture, Taps, Shower head, Health Faucet – Hindware, somany or Equivalent Other Toilet Fixtures- Same as above.

- Kitchen Sink Provided with SS Branded type, Long Body Bib Cock.
- Rain water pipe from Terrace to ground floor.
- Rain water harvesting will be Extra chargeable
- Laying required dia pipe & fixing from toilet, bathroom, kitchen sink to septic tank and soak pit.
- Sock pit forming with excavation, precast RCC lining will extra chargeable.

➤ **ELECTRICAL:**

- All electrical wiring with concealed PVC conduits from switch board with required MCB wise) till main electrical board.
- Hall Living area - 1no TV point, 3 no's 6 Amps socket and switches, 2 no's light point, 1 no Night lamp, 2 no's Fan point with regulator, Primary switch board including 1 no 6 Amps switch and socket, 1 no decoration light point.
- Bedrooms/Dining – 2 no's light point, Amps switch 1 no fan point, Primary switch board including 2 no 6 and socket, 1 no A/C point, 1 Nigh lamp
- Toilet- 1 no wall light, 1 no 15 Amps switch and socket for Heater, 1 no exhaust fan point
- Kitchen - 2no's ceiling socket. light, 3 no's 6 Amps switch and socket, 2 no's 16 Amps switch and socket.
- DB with required MCB and Phase changer in every portion.
- External light points in car/bike parking, Staircase & balcony area, 16 amps for motor, light points in terrace.
- All switches will be GM, Legrand switches, sockets, wiring with concealed type with conduit using orbit wires or Kundan.
- Extra points each1-no Ordinary point, Rs:800 charges applied.
 - a. A/C points: Rs:5000/-
 - b. 6 Amps: Rs: - 900/-
 - c. 16 Amps: Rs: - 2000/-
 - d. CCTV: Rs: -5000/-
- Inverter, CCTV, water tank Automation cut off Switch and Spot Light are extra chargeable.

➤ **FINISHING:**

- All Flooring Tile- Size 2"x2" KAG vitrified tile of Basic cost Rs.45 per Sq. ft and same as Skirting.
- Toilet Wall Dado- 12"x 8"or 12" x 12" up to 7 feet height of basic cost Rs.40 per Sq. ft.
- Kitchen table top with Black Granite over RCC slab Counter (Granite will be provided in Single side of table top), Tile Dado will 4feet high and S.S.Sink.
- Internal ceiling 1 coat primer with 2 coat (tractor) emulsion (Asian) & wall 2 coat Putty, one coat primer with 2 coat (tractor) emulsion with approval colour. (Same colour Will be adopted for Internal Walls).
- External one coat Primer and two coat Asian Ace with approval colour.
- Staircase & Parking area will be finished with anti-skid tiles costing Rs. 35/- per Sq. ft same adopted for Skirting.
- Staircase Hand rail Will be done with M S tubular Section with Black Enamel painted.

- Balcony Hand rail Will be done with SS tubular Section-extra chargeable
- Window Grills will be done with simple design of MS square bar size 12mm and finished with Black Enamel paint.
- Terrace flooring will be finished with concrete 1:2:4 Required slope & top finish 1:5 plastering.
- Elevation tiles on main door area, front elevation for builder area labour charges, Materials including tiles cost extra by owner.

➤ **ITEMS WITH ADDITIONAL COST:**

- Septic tank sumps with RCC Raft Rs.23/-per litre
- Hollow block Compound Wall-Rs.1750/- per Running feet excluding MS tubular gate.
- Staircase, upgradation from tile to granite will be extra charge.
- Bore well with motor & TNEB service connection (Main Board fitting for 3 phase connection)
- Sump at car parking and Overhead water tank - RCC columns, slab & cover slab with plastering, water proofing finishing - Rs. 23/- per litre. Wall & floor tile inside tank with epoxy jointed will be additional chargeable.
- Front Elevation Design works & Tile fixing will be additional chargeable.
- Cost of compound wallgate-Rs-120/per kg including enamel paint.
- TNEB power for construction & cost of power for water required during construction.

AREA WITH PAYMENT SCHEDULE

Basement:

SI.NO	Location in Building	Measure ment	Rate	Amount
1	Ground floor	1102-Sq.ft	2200/-	24,24,400/-
2	Septic tank	12000 Ltrs	18/-	2,16,000/-
3	Extra 2'-0 Basement height	2'- feet	L.S	1,40,000/-
			Total	27,80,400/-

Payment Schedule:

1	Before Ground Floor Basement	30%	8,34,120/-
2	Before Ground Floor Roof Level	30%	8,34,120/-
3	Before Ground Floor Wood window frame work and electrical work, wall cutting & switch board fitting, plumbing, toilet CPVC pipe fitting, inner plastering work	15%	4,17,060/-
4	Before outer Plastering work and tile work, Electrical, Plumbing work	15%	4,17,060/-
5	Before complete all civil work, plastering work, tile, plumbing, electrical work etc.	10%	2,78,040/-
		Total	27,80,400

As per additional requirement of the clients where they should be an additional cost

OWNER

CONTRACTOR

WITNESS